

PREVENTIV

EMERTIMI: "Rikonstruksioni i Rrugës Qender Gose-Hekurudha-Gose e Madhe, Bashkia Rrogozhinë"
Gjatesia L=1600m (Dega Nr.1+ Dega Nr.2)

N.r	Nr. Anal.	Pershkrimi	Njesia	Sasia	Çmimi (Leke)	Vlera (Leke)
I- PUNIME PER TRUPIN E RRUGES						
1	3.89/b	Germim dheu	m ³	7,040.0		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	7,040.0		-
3	An-49	Prishje Betoni	m ³	60.0		-
3	2.426/2	Prishje mur blloqe betoni	m ³	150.0		-
4	An.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	1,960.0		-
5	An.164/1b	Shtrese çakelli mbeturine kave t=30(2x15)cm, perhapur e ngjeshur makineri	m ³	3,285.0		-
6	An. 3.212/b	Shtrese, stabilizant, 8cm per bankinat	m ²	1,892.0		-
7	3.212/b	Shtrese, stabilizant, 10cm per rruget dytesore	m ²	550.0		-
8	3.212/d	Shtrese stabilizant t=20cm	m ²	10,810.0		-
9	3.222/1	Shtrese binderi, me granil gure kave , 5 cm, perhapur e ngjeshur me makineri	m ²	8,010.0		-
10	3.224/1	Shtrese asfaltobetoni me granil gure kave , 3 cm, perhapur e ngjeshur me makineri e ngjeshur me makineri	m ²	8,010.0		-
Shuma 1						-
II- PUNIME NE TROTUAR						
1	3.89/b	Germim dheu	m ³	44.0		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	44.0		-
3	An.164/1b	Shtrese çakelli t=20cm, perhapur e ngjeshur makineri	m ³	36.0		-
4	3.243	Beton C 16/20 per shtrese trotuari t=10cm	m ³	18.0		-
5	3.243	Beton C 16/20 per bordure monolite 10x25cm	m ³	6.6		-
6	2.261	F.V. Rere per shtrese trotuari t=4cm	m ³	5.4		-
7	AN	FV pllaka betoni te presuara t=6 cm	m ²	180.0		-
8	3.618	F V bordura betoni 20x35 cm	ml	750.0		-
Shuma 2						-
III- VEPRA ARTI						
Mure Mbajtes/Prites						
1	3.89/b	Germim dheu	m ³	360.0		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	360.0		-
3	3.243	Beton C 16/20 per mure mbajtes e prites	m ³	578.2		-
4	An-8	Mbushje me cakell pas mureve	m ³	273.0		-
5	An-10	Mbushje me argjile pas mureve	m ³	42.0		-
6	An.164/1b	Shtrese cakelli t=10cm per nivelim	m ³	43.0		-
7	2.519	Furnizim, vendosje tuba pvc ø 90	ml	151.0		-
Tombino Rrethore						-
8	3.89/b	Germim dheu per tombino dhe portale	m ³	350.0		-
9	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	350.0		-
10	3.364	Tombino me tuba betoni Ø 500, mbi shtrese betoni	m	34.0		-
11	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	m	11.0		-
12	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	m	10.0		-
13	3.240	Beton C 12/15 per veshje tombino	m ³	26.0		-
14	An-9	Shtrese zhavorri t=10cm	m ³	11.0		-

15	3.243	Beton C 16/20 per puseta e portale	m ³	68.0	-
Tombino Box					
16	3.89/b	Germim dheu per tombino kuti dhe portale	m ³	1,640.0	-
17	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	1,640.0	-
18	3.245	Beton C 25/30	m ³	331.1	-
19	3.288	F V hekur betoni	ton	28.55	-
20	3.240	Beton C 12/15	m ³	74.0	-
21	An-9	Mbushje me zhavorr (per nenshtrese)	m ³	177.0	-
22	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m ²	158.0	-
23	An-8	Mbushje me cakell	m ³	220.0	-
Ure HD=4ml					
24	3.89/b	Germim dheu per tombino kuti dhe portale	m ³	210.0	-
25	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	210.0	-
26	3.245	Beton C 25/30 per soleton	m ³	9.7	-
27	3.245	Beton C 25/30 per soleta rakorduese	m ³	4.2	-
28	3.244	Beton C 20/25 per ballnat dhe muret	m ³	128.0	-
29	3.288	F V hekur betoni	ton	1.90	-
30	3.240	Beton C 12/15	m ³	3.0	-
31	An-9	Mbushje me zhavorr (per nenshtrese)	m ³	6.2	-
32	2.197	Hidroizolim me emulsion bitumi dhe 2 shtrese k katrama	m ²	32.2	-
33	An-8	Mbushje me cakell	m ³	26.0	-
Shuma 3					
IV- PUNIME NE KANALIZIMET E UJRAVE TE SHIUT dhe KUZ					
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi deri 2 m, toke zak, kategoria III, me shk ne mjet	m ³	340.00	-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	340.00	-
3	3.244	Beton C 20/25 per kuneta, t=10cm	m ³	45.25	-
4	An - 23/M2	Pusete b/a shiu 40 x 60, h = 100 cm, (kapak kompozit)	cope	27.00	-
5	An - 20	Pusete kontrolli b/a, 80 x 80 cm, h = 150 cm	cope	11.00	-
6	2.523/1	F.V Tuba PVC f=200 mm te brinjezuar	ml	150.00	-
7	2.261	Shtrese rere perreth tubit f=200mm	m ³	8.00	-
8	3.An/1t	F V tuba te brinjezuar HDPE SN8 d=315 mm (perfshi reren per mbrojtjen e tubit)	ml	551.00	-
9	3.An/2t	F V tuba te brinjezuar HDPE SN8 d=400 mm (perfshi reren per mbrojtjen e tubit)	ml	427.00	-
10	3.An/3t	F V tuba te brinjezuar HDPE SN8 d=500 mm (perfshi reren per mbrojtjen e tubit)	ml	41.00	-
11	3.An/4t	F V tuba te brinjezuar HDPE SN8 d=600 mm (perfshi reren per mbrojtjen e tubit)	ml	68.00	-
12	2.258	Mbushje me zhavorr nen pusete	m ³	1.60	-
13	An.164/1b	Mbushje me cakell mbi tub	m ³	110.00	-
Shuma 4					
V- PUNIME PER NDRIÇIMIN RRUGOR					
1	3.An/53	F.V. Shtylle metalike H=7.8ml. 4mm	cope	9.00	0
2	3.An	FV ndricues Smart 250W 230V	cope	9.00	0
3	3.An/ksh	F.V. krah nje degesh (150)	cope	9.00	0
4	3.An/et	FV elektroda tokezimi te xinguara 50x3mm, L=150cm	cope	13.50	0
5	AN	FV Morseteri shtylle 3P+sig10A+kapak	cope	9.00	0
6	2.481/5	F.V percjelles PV-500 Ø 10 mm2	ml	230.00	0
7	2.481/2	F.V percjelles PV-500 Ø 2.5 mm2	ml	90.00	0
8	3.An/pp	FV pusete plastike 40x40x40, kapak te forte RIC 1084+1086	cope	9.00	0
9	An/M3	F V kuader komandimi komplet me santeri+fotoelement	cope	1.00	0
10	2.519	Tub pvc Ø 90 mm	ml	220.00	0
11	2.261	F.V. Rere per fiksim shtyllash	m ³	0.10	0
12	3.24	BetonC 12/15 per inkastrim shtylle	m ³	0.40	0
13	An	Spostimi i linjave elektrike ekzistuese TM (linje dhe dy shtylla)	ml	80.0	0
Shuma 5					

VI- PUNIME PER RRJETIN INXHINIERIK NENTOKESOR						
1	3.654/1	Furnizim, vendosje tuba l brinjezuar fleksibel ø 80	ml	660.00		-
2	An/M3	F.V. Tub metalik D = 140mm	ml	20.00		-
3	An - 20	Pusete kontrolli b/a, 80 x 80 cm, h = 150 cm	cope	4.00		-
4	2.261	F.V. Rere nen dhe mbi tubacione + kompakesim	m ³	4.00		-
Shuma 6						
VII- PUNIME PER SINJALISTIKEN						
1	An122	Vijezim shirita gjatesor dhe anesor me gjeresi 12 cm, Bikomponent (sprajt)	ml	3,258.0		-
2	An143	Boje bikomponente (paste), kembesor etj	m ²	23.5		-
3	AN -158	F.V. Tabela 60x60cm	cope	4.0		-
4	An-155	F V tabela rrugore STOP	cope	14.0		-
5	An105	F.V. Tabela Trekendore 60cm	cope	34.0		-
6	An102	F.V. Tabela Rrethore D=40	cope	17.0		-
7	An116	Delineator	cope	40.0		-
8	An119	Pervijues modular kthese, cift 60x60cm	cope	16.0		-
9	An64	Sinjalet e drejtimet urban HxL normal 25x125	cope	10.0		-
10	An3	Guardrail- N2 anesore me 2 valez. ne 1 ane , W4 + aksesoret	ml	438.0		-
11	An22	Guardrail H2 anesore per ure me 2 vale ne 1 ane+handrail ,W5 + aksesoret	ml	66.0		-
Shuma 7						
VIII- PUNIME PER MURIN RRETHUES						
1	3.89/b	Germim shtresa ekzistuese	m ³	90.0		-
2	3.158/5a	Transport dheu me auto deri 5.0 km	m ³	90.0		-
3	2.109/2	Themel e xokol betoni C - 12/15	m ³	40.00		-
4	2.111/2	Mure blloqe betoni 20cm	m ³	70.00		-
5	3.244	Beton C 20/25 per kollona	m ³	6.00		-
6	3.288	F V hekur betoni i zakonshem Ø > 12mm	ton	1.2		-
Shuma 8						
Total (1-8)						
		Fondi rezerve %	5.0%			-
		Shuma pa TVSH				-
		TVSH %	20%			-
		Shuma me TVSH				-