

PREVENTIV

Objekti: RIKONSTRUKSIONI I RRUGES KRYQEZIMI AKSI NACIONAL – SEKTORI III, LUFTINJE (Faza I, L=5000 ml), BASHKIA MEMALIAJ

Nr.	Analiza	Pershkrimi i Punimeve	Njesia	Sasia	Çmimi (lek)	Vlefte (lek)
I. PUNIME PER EVADIMIN E MBETURINAVE DHE REHABILITIM TE ZONAVE KU JANE PRISHUR NDERTESAT DHE GJELBERIMI						
1	3.137	Germim dheu me ekskavator goma 0.15 m ³ , ne themele, toke zak, kategoria III, me shkarkim ne toke	m ³	1,050		
2	An-49	Prishje struktura prej betoni	m ³	140		
3	3.158/2a	Transport dheu me auto deri 2.0 km	m ³	21,317		
4	An-50- M3	Transport element betoni dhe b/a me auto deri 10 km	ton	140		
Shuma I						
II. PUNIME PER NDERTIMIN E RRUGES						
1	3.137	Germim dheu me ekskavator goma 0.15 m ³ , ne themele, toke zak, kategoria III, me shkarkim ne toke	m ³	31,343		
2	An.164/1a	Mbushje me material te germuar ne trupin e rruges, perhapur e ngjeshur me makineri	m ³	11,076		
3	3.240	Shtrese betoni C12/15	m ³	220		
4	3.244	F.V. Beton C20/25 per vepra arti	m ²	800		
5	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur makineri	m ²	32,500		
6	An	Shtrese e stabilizuar me ELJ t=20cm	m ²	32,500		
7	3.212/a	Shtrese stabilizanti t=5cm	m ²	7,500		
8	3.226/2	Shtrese asfaltobetoni me granil guri kave, 5cm, me makineri	m ²	25,000		
9	3.287	F V hekur betoni i zakonshem Ø 6 ~ 10mm	ton	15		
10	An-M3	Skarifikim shtrese asfalti me makineri	m ²	27,491		
Shuma II						
III. PUNIME PER KUB						
1	3.379	F.V. Rere nen dhe mbi tubacione PE + kompaktesim	m ³	450		
2	An-9 M3	F.V. Zhavorr ne kanale + ngjeshje me shtresa cdo 25cm	m ³	880		

3	3.An/1t	F.V tuba I brinjezuar Ø 315 mm	ml	260		
4	3.365	Tombino me tuba betoni Ø 600, mbi shtrese betoni	ml	22		
5	3.366	Tombino me tuba betoni Ø 800, mbi shtrese betoni	ml	44		
6	3.367	Tombino me tuba betoni Ø 1000, mbi shtrese betoni	ml	164		
7	3.368	Tombino me tuba betoni Ø 1200, mbi shtrese betoni	ml	12		
8	An - 22/1	Pusete b/a shiu 40 x 40 cm, h = 100 cm, me kapak zgare hekuri	cope	8		
9	2.523/1	F.V tuba I brinjezuar Ø 200 mm	ml	292		
					Shuma III	
IV. PUNIME SINJALISTIKE RRUGORE						
1	An1- Man3	Guardrail- N2 anesore me 2 valez. ne 1 ane , W2 + aksesori	ml	150		
2	An146	Boje termoplastike (paste)	m ²	65		
3	An99	Tabele sinjalistike	cope	13		
4	2.110/2	Shtrese butobetoni C - 12/15	m ³	13		
					Shuma IV	
					SHUMA I - IV	
					FONDI REZERVE 5%	
					SHUMA	
					T.V.SH. 20%	
					SHUMA TOTALE	