

Projektuesi: B.O.E "HYDRO-ENG CONSULTING"
sh.p.k & "ENGINEERING CONSULTING
GROUP" sh.p.k & "SIRE-ALB" sh.p.k

Objekti: Rikonstruksion i rruges ,K.U.B-ne ne bllokun
e pallateve Shen Vasil.

Datë: 15-07-2026

PREVENTIV

NR.	KODI	EMËRTIMI I PUNIMEVE	NJËSIA	SASIA	ÇMIMI	VLEFTA
		1. PUNIME GERMIMI				
1	3.89/b	Germim dheu me ekskavator goma 0.25 m ³ , ne kanale gjeresi > 2 m, toke zak, kategoria III, me shk ne mjet >	m3	1388.0		
		Shuma 1:				
		2. PRISHJE				
2	2.426/3	Prishje shtresa betoni >	m3	16.0		
3	2.426/2	Prishje mur blloqe betoni >	m3	15.0		
		Shuma 2:				
		3. PUNIME DHEU				
4	2.37/2b	Transport materiale ndertimi, dheu me auto deri 7.0 km >	m3	1388.0		
		Shuma 3:				
		4. PUNIME SHITESASH				
5	3.164/1b	Mbushje me cakell e gur gurore ne trupin e rruges, perhapur e ngjeshur me makineri >	m3	35.0		
6	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri >	m2	1350.0		
7	3.211	Shtrese çakelli mbeturine kave t=20cm, perhapur e ngjeshur me makineri >	m2	1350.0		
8	3.212/c	Shtrese stabilizant t=15cm >	m2	1350.0		
9	3.210	Shtrese çakelli mbeturine kave t=15cm, perhapur e ngjeshur me makineri >	m2	2410.0		
		Shuma 4:				
		5. NDERTIMI I VEPRAVE TE ARTIT+KANALIZIME				



10	3.581	Mbingritje h=0.5 m, Pusete ekzistuese UZ Φ 1.0 m >	copë	12.0		
11	3.588	Ndertim Pusete kontrolli Elektrotelefoni, me kapak gize, 1.0x1.0x1.0 m >	copë	10.0		
		Shuma 5:				
		6. INSTALIME HIDRO-SANITARE DHE NGROHJE				
12	2.523/1	F.V. Tuba PVC f=200 mm te brinjezuar >	ml	490.0		
		Shuma 6:				
		7. TE NDRYSHME, ELEKTRIKE DHE SINJALISTIKA				
13	3.164/1t	F.V. Tuba te brinjezuar HDPE SN8 d=315 mm >	ml	280.0		
14	3.176	F.V. Pusete plastike 40x40x40, kapak te forte RIC 1084+1086 >	copë	15.0		
15	3.933	F.V. Tabela tete kendore e vogel me A-B, 60-20 >	copë	1.0		
		Shuma 7:				
		8. UJESJELLES E KANALIZIM I JASHEM				
16	2.342	Pusete shiu 40 x 60, h = 100 cm, me kapak gize >	copë	10.0		
		Shuma 8:				
		9. PUNIME MURATURE GURI				
17	2.88	Mur me blloqe betoni 20cm, deri - 3m, me LL.P. M-15 >	m3	15.0		
		Shuma 9:				
		10. PUNIME BETONI E BETONARMEJE				
18	3.243	Struktura monolite betoni C 16/20 >	m3	55.0		
		Shuma 10:				
		11. PUNIME TE NDRYSHME				
19	3.616/a	F.V. Bordura betoni 15x25cm >	m	590.0		
20	3.620	Trotuar, me 6 cm beton, me pllaka >	m2	2404.89		



		Shuma 11:				
		12. D. SINJALET DHE PAJISJET SHITESH. NGADALESUESIT E SHPEJTESISË				
21	3.966	F.V. Mbajllje peme dekorative Bli 16-18cm ne trotuar, (cdo 6m) >	copë	25.0		
22	3.955	F.V. Tabela te ndryshme rrugore D=60cm >	copë	5.0		
		Shuma 12:				
		13. ANALIZA TEKNIKE				
23	3.222/2	Shtrese binderi me granil gur kave,6cm,me makineri >	m2	1250.0		
24	3.226/1	Shtrese asfaltobetoni me granil guri kave, 4cm, me makineri >	m2	1250.0		
		Shuma 13:				
		14. B. SINJALET HORIZONTALE				
25	3.942	Vijejim shirita gjatesor dhe anesor me gjeresi 12 cm. Bikoponente (sprajt) >	ml	486.0		
		Shuma 14:				
		15. PUNIME HEKUR BETONI				
26	2.166	F.V. Hekur betoni periodik Ø 6 - 10 mm >	ton	0.78		
27	2.166/1a	F.V. Hekur betoni periodik Ø > 12 mm >	ton	5.7		
		Shuma 15:				
Shuma Analiza						
Fondi Rezervë (5.0%)						
Shuma Analiza + Fondi Rezervë (5.0%)						
TVSH (20%)						
Shuma me TVSH						
Totali						

**Preventivuesi:**

B.O.E "HYDRO-ENG CONSULTING" sh.p.k &
 "ENGINEERING CONSULTING GROUP" sh.p.k
 & "SIRE-ALB" sh.p.k

Investitori:

Bashkia Himarë